

SCHEDULE 35

Barrow Scope of Work

This is Schedule 35 comprising the Barrow Scope of Works as referred to in the Project Agreement
for the provision of waste services to Cumbria

between

CUMBRIA COUNTY COUNCIL

and

SHANKS CUMBRIA LIMITED



DICKINSON DEES

Dickinson Dees LLP

St Ann's Wharf 112 Quayside Newcastle upon Tyne NE1 3DX

Telephone: (0191) 279 9000 Fax: (0191) 279 9100

Email: law@dickinson-dees.com www.dickinson-dees.com

SCHEDULE 35

Barrow Scope of Work

SOUTHERN RESOURCE PARK BARROW
GENERAL ITEMS - ENABLING WORKS
Description
The provisional sum includes: <ul style="list-style-type: none">• Treatment of contaminated ground

SOUTHERN RESOURCE PARK - FOUNDATIONS
Description
The provisional sum includes the cost of: <ul style="list-style-type: none">• Installation of 130 no cfa piles to average depth of 4.5m to accommodate a max swl of 450 kn, pile dia 450mm, concrete grade 30n/mm2• Pile caps• Testing on piles and concrete
For the avoidance of doubt the provisional sum excludes the following which are included within the Building Contract Price <ul style="list-style-type: none">• Excavation and disposal except for where this is related to excavation and disposal of ground contamination• Pit construction except for where increased cost of construction relates to ground conditions• Ground Anchors

SOUTHERN RESOURCE PARK - UTILITIES
Description
The provisional sum includes:

- Utility connections (electricity, water), both to and within the site
- Electricity sub-station (if required)
- Upgrade of network to supply power to sub-station